



The City of Lorain, Ohio

ADDENDUM #3 OPWC 36A

March 22, 2023

The following enumerations contain answers to questions from plan holders. **The City's response is in red font.**

1. The estimated quantities for pavement removal, subgrade compaction, excavation, and aggregate base are all based on Item 7 – 8” PCC Finish Pavement. But, the quantity for Item 8 – 8” PCC for Boxout should also be included.

The items Pavement Removal, Subgrade Compaction, Excavation and Aggregate base INCLUDE the boxouts; there is no separate item for boxout removal as they are removed when the 8” pavement is, and the Subgrade Compaction, Excavation and Aggregate base are accounted for.

2. Item 15 “Type 2-A Curb”, 24 LF as indicated on plan sheet 9 appears to actually be the removal and replacement of either Type 2 (curb and gutter), or Type 6. Type 2-A, per BP-5.1 is just the integral curb on a slab. Also, there needs to be a corresponding removal bid item.

Add new item (Number 36) Type 6 Curb Removed, quantity is 24 LF.

3. Items 31-35 quantities on bid form do not match quantities on General Summary plan sheet 4.

Change item 15 from Type 2 Curb to Type 6 Curb. (quantity remains 24 LF)

4. These changes may affect the Engineer's Estimate of Cost.

Quantities for items on bidsheet should be as follows (it will match the General Summary in the Plans):

31. Stop Bar, Type 1 - **158 LF**
32. Crosswalk - **740 LF**
33. Topsoil, Furnished and Placed – **245.7 CY**
34. Seeding and Mulching with Fertilizer – Hydroseeding Req. 3/1 – 10/30. – **2234.9**
35. Inlet Protection – Dandy Sack – **16**

**NO MORE QUESTIONS SHALL BE ANSWERED THROUGH ADDENDA
PURSUANT TO THE 72-HOUR RULE**

ALL ADDENDA MUST BE ACKNOWLEDGED ON PAGE 26 OF THE BID PACKAGE

THE BID OPENING SHALL TAKE PLACE AT 11:35 A.M. ON 3/27/2023